

### Quotation

M/s. Naba Ballygunge Mahavidyalaya

27E, Bosepukur Road, Kolkata-42.

Sl. No	Descriptions	Qty.	Rate (Rs.)	Amount (Rs.)
	<b>Principal Room :</b>			
1.	<b>Drop Ceiling with side Trey</b> Providing and fixing Flase Ceiling with drops, verticals, fascias, made of standard GI sections and 12mm thick Gypsum board sheets as per "Sen Gobin" Specifications. The ceiling should be inclusive of all hangers, edge members and other clips complete. Sheets shall be fixed with proper fasteners inserted with power drills. The joints must be duly finished ensuring level in line and plumb. The whole ceiling must be ready to take final paint. The GI grid shall have a spacing of 1200mm x 600mm, including GI Corner beads, edge trims and other accessories. Finishing includes marking and doing all specified cut outs and providing additional supports for light fittings, air conditioning grills, diffusers etc. completed.	710 sft.		
2.	Supply & fixing of Roller Blinds (As per approve shade)	.100sft.		
3.	<b>Wall Paneling :</b> 2x1 C.P.Wooden structure with proper screw and both side 12.0mm century ply fixing and 4.0mm century Veneer pasting with PU finished all complete.	250 sft.		
4.	Door Frame 12.0mm Century ply pasting and 4.0mm veneer pasting with PU finished all complete. (4 pcs.)	68 sft.		
5.	Old Door Palla modify & re-fixing with bearing hinges and both side 12.0mm Century ply & 4.0mm Century veneer pasting and PU finished all complete. (door size-7ft.x3.5ft.)	4 pcs.		
6.	<b>Painting works :</b>			
	(i). <b>Wall Putty :</b> Prepare to smooth surface applying Asian Paint putty	1650 sft.		
	(ii). Applying 3 coats of Royal Paint(Asian) and applying 3 coated cement primer. All painting on jambs, trims, edges, grooves to be included in SQM rate. No separate measurement on RMT shall be entertained. Finishing must be done with a roller.	1650 sft.		

Sl. No	Descriptions	Qty.	Rate (Rs.)	Amount (Rs.)
	(iii). Texture Paint : Applying texture paint as per design and of the shade approved on walls as indicated. Cost is inclusive of preparing the surface, applying paint, and finishing	650 sft.		
			Total	
	<i>Rupees in words:</i> .....			